# BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE
## Office of the Executive Engineer, Dasarahalli Division
Schedule _B

NAME OF THE WORK: Improvements & construction of drainage works old post office road at Dasarahalli in ward no. 15 Dasarahalli sub division

| Sl. No | Description of work | Unit | Qty | Rate Quoted by Ramachandra | |
|---|---|---|---|---|---|
| | | | | In Figures (Rs.) | In Words (Rs.) |
| 1 | 2 | 3 | 4 | 5 | 6 |
| 1 | KSRRB 300 - Excavation for road, drains and similar works - KSRRB 300-1. Earthwork excavation by manual means in Ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH Chapter 3 (P.142/I.19.1 PW, P & IWTD -SR 2016-17) | **Cum** | 229.50 | 80.0 | Rupees Eighty Only |
| 2 | KSRRB M2100-10. Plain cement concrete M-10 with OPC cement at 220kg with crushed 40mm down size graded granite metal course aggregate @0.84 CUM and fine agreegate @ 0.6 CM in Foundation mechanically mixed placced in foundation and compacted by vibration including curing for 14 days complete as per specifications. MORTH Specification No. 2100. Page No. 218/ Item No. 27.18/ PWD SR 2016-17 | Cum | 37.65 | 5521.0 | Rupees Five Thousand Five Hundred Twenty One Only |
| 3 | KSRB 4-6.3: Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness above 200 mm including cost of all materials, labour complete as per specifications.(Page No: 15, itno: 4.30) 2016-17 | Sqm | 742.20 | 376.0 | Rupees Three Hundred Seventy Six Only |
| 4 | KSRB M2200-5.9 Design Mix M20 with OPC cement @ 320kgs with 20mm & down size graded granite metal course agreegate @ 0.69 CM an Fine agregated 0.46 cm with super plaster @ 3ltrs confirming to IS 9103-1999 Reaffirmed -2008 i.) Upto 5m height Page No. 223/ Item No. 28.7.9/ PWD SR 2016-17 | Cum | 101.66 | 6439.0 | Rupees Six Thousand Four Hundred Thirty Nine Only |

Signature of the Contractor

Executive Engineer,
Dasarahalli Divison,
BBMP

| | | | | | |
|---|---|---|---|---|---|
| 5 | KSRB M-2200- TMT/MS bar Reinforcement KSRRB M2200-6 Supplying, fitting and placing TMT bar reinforcement in Sub-structure complete as per drawing and technical specifications complete as per specifications. MORTH specification No. 1600 & 2200. Page No. 225/ Item No. 28.8/ PWD SR 2016-17 TMT Bars FE 550 | Tonne | 6.81 | 54373.0 | Rupees Fifty Four Thousand Three Hundred Seventy Three Only |
| 6 | Supplying and fixing precast rainforced concee slab 10cm thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface stc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials. | Cum | 189.00 | 1479.0 | Rupees One Thousand Four Hundred Seventy Nine Only |
| 7 | Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading Page No. 150 Item No. 17.1 PWD SR 2016-17 | Cum | 229.50 | 75.0 | Rupees Seventy Five Only |

Signature of the Contractor

Executive engineer,
Dasarahalli Divison,
BBMP